8. On acceptance of one of the tenders, the earnest money on rejected tenders will be returned.

Bund.—Earthwork (Maximum height 50')	..	C. Yd.	1,42,022
Stone work	..	Do	7,122
Clearing sand	..	Do	25,872
Sluice and Weir.—Brick in chunam (surki)	..	per C. Ft.	
Burnt stone in surki chunam ..	..	Do	
Burnt stone slabs 6" ..	..	per Sq. Ft.	
Do 8"	..	Do	
Gears for sluices	..	Each.	
Grade stones	..	16.	
B. Ms. Stones	..	2.	

Y. SRINIVASA RAO,
Executive Engineer.

MYSORE DIVISION.

ADVERTISEMENT.

The 24th June 1888.

Notice is hereby given that sealed tenders will be received at the office of the Executive Engineer, Mysore Division, up to 10th July 1888 for restoring Kikere Amani Tank, Registered No. 191 of Attikuppa Taluk. An approximate estimate of quantities is given below. These quantities are not guaranteed. The work should be completed by the end of April 1889.

2. The plans, detailed estimate and conditions may be seen at the Executive Engineer's office at Mysore between the hours of 11 A. M. to 5 P. M.

3. Tenders should be submitted on printed forms which may be obtained from the Executive Engineer. The tenders should be accompanied by a statement in the form given below, showing the rates at which the different items specified will be executed :—

Items of Work.	Per.	Bund.	Waste Weir.	Waste Weir Channel.	Total.	Rate.	Cost.
Earthwork	C. Yd.	3,719	..	..	3,719		
Old stone work	Do	400	..	..	400		
New do	Do	66	..	16	82		
Grade stones	Nos.	43	..	..	43		
Excavation, soft soil	C Yd.	..	15	16	31		
Do soft rock	Do	..	394	34	428		
Rough stone in mortar hearting ..	C. Ft.	..	13,679	..	13,679		
Hammer dressed, do for face ..	Do	..	2,478	..	2,478		
Brick in surki mortar	Do	..	7,126	5,291	12,417		
Plastering with chunam	Sqr.	..	25·63	7·16	32·79		
Pointing with chunam	Do	..	43·72	..	43·72		
Stone slabs	C. Ft.	..	594	142	736		
Dry stone revetment	C. Yd.	..	218	..	218		
Earthwork for bank	Do	..	440	..	440		

4. Each tender must be accompanied by a deposit of Rs. 50—0—0 in cash or Government promissory notes as earnest money, and be superscribed "Tender for restoring Kikere Amani Tank, Registered No. 191 of Attikuppa Taluk," in default of which, tenders will be rejected.

5. The final acceptance of any tender will rest with the Superintending Engineer, who does not bind himself to accept the lowest or any tender or to assign any reason whatever for the rejection of any tender.

6. Within 8 days of the acceptance of the tender, the successful competitor will be required to execute the usual contract bond ; in default of which, his tender will be considered cancelled and his earnest money will be forfeited.

7. The name of the successful competitor, whose tender has been accepted, will be posted on the notice board in the Executive Engineer's Office in due course. No enquiries regarding the acceptance or rejection of a tender will receive any reply.

8. On acceptance of one of the tenders, the earnest money on rejected tenders will be returned.

V. H. KARVE, L. C. E.,
Executive Engineer.